

Vicinity Map
A NORTH
AI

SHEET SCHEDULE

- AI Layout, Development Summary
- C1 Existing Conditions
- C2 Grading & Utilities
- A2 Landscape Plan, Building Elevation Studies

GENERAL INFORMATION

COUNCIL DISTRICT INFORMATION:

Council District 15
Councilmember Phil Claiborne

PROPERTY INFORMATION

410 Donelson Pike (a portion of Map 96-09, Parcel 74)
Nashville, Tennessee 37214
2.04 Total Acres
Council District 15 (Councilmember Phil Claiborne)

OWNERS OF RECORD

Ron Gnzard and Frank Batson
120 Donelson Pike
Nashville, Tennessee 37214

DEVELOPER


Ron Gnzard and Frank Batson
120 Donelson Pike
Nashville, Tennessee 37214

ARCHITECT

Third Coast Design Studio
1201 Villa Place, Suite 104B
Nashville, Tennessee 37212
Contact: Keith Covington, RA
Phone: 615.678.8640
Email: keith@thirdcoast.designstudio.com

CIVIL ENGINEER

Joseph C. McConnell, PE
400 Breeze Point
Hermitage, Tennessee 37076
Contact: Joseph C. McConnell, PE
Phone: 615.207.6876
Email: joeconnell@comcast.net



B NORTH
AI

GENERAL PLAN CONSISTENCY NOTE

This project is located within the Donelson - Hermitage - Old Hickory Community Plan's T3 Suburban Neighborhood Maintenance and the District Office Concentration policy areas.

T3 Suburban Neighborhood Maintenance

The T3 Suburban Neighborhood Maintenance policy classification is intended to preserve the general character of suburban neighborhoods. This proposal is consistent with the overarching intent of the policy area, because efforts have been made to retain the existing character of the neighborhood, in terms of its development pattern, building form, land use, and the public realm. The scale and rhythm of existing houses across Lakeland Drive steered the original design concept for the development, and the existing context ultimately dictated the pattern of the proposed development. All of the proposed land uses within the T3 Suburban Neighborhood Maintenance policy area are single family detached houses, matching the adjacent land uses within the same policy area. The project includes inviting, functional, and accessible open spaces as an integral part of the development. The primary open space provided on the plan within this policy area is a large formal green that will serve multiple purposes, including a rain garden that will serve as a storm water management device, as well as a central gathering space for all of the residents. Sidewalks will be provided along Lakeland Drive, as well as throughout the common spaces of the development. Parking is screened from public view, and every effort has been made to make primary facades visible from the street and common spaces.

District Office Concentration

The District Office Concentration policy classification is intended to preserve, enhance, and create Districts where office use is predominant and could be supplemented with complementary uses. This district is intended to encourage development in a manner that is complementary of adjacent development patterns, building forms, and land uses. Medium to high density residential development is appropriate in this policy area, especially as a transition to lower density residential areas in adjacent policies. The proposed SP is consistent with the District Office Concentration policy, because it has been designed to correspond with the varying adjacent context in terms of massing, scale, setback, and land uses. This SP will provide a complementary transition through changes in building form and massing from the higher intensities present and fronting on Donelson Pike.

STANDARD SP NOTES

- The purpose of this SP is to receive preliminary approval to permit the development of a 15-unit residential development.
- Any excavation, fill or disturbance of the existing ground elevation must be done in accordance with Storm Water Management Ordinance no. 78-840 & approved by the Metropolitan Department of Water Services.
- All public sidewalks are to be constructed in conformance with Metro Public Works sidewalk design standards.
- Wheel chair accessible curb ramps, complying with applicable Metro Public Works standards, shall be constructed at street crossings.
- The required fire flow shall be determined by the Metropolitan Fire Marshal's office, prior to the issuance of a building permit.
- Size driveway culverts per the design criteria set forth by the Metro Stormwater Manual.
- Metro water services shall be provided sufficient and unencumbered ingress & egress at all times in order to maintain, repair, replace and inspect any stormwater facilities within the property.
- Minor modifications to the Preliminary SP Plan may be approved by the Planning Commission or its designee based upon final architectural, engineering or site design and actual site conditions. All modifications shall be consistent with the principles and further the objectives of the approved plan. Modifications shall not be permitted, except through an Ordinance approved by Metro Council that increase the permitted density or floor area, add uses not otherwise permitted, eliminate specific conditions or requirements contained in the plan as adopted through this enacting ordinance, or add vehicular access points not currently present or approved.
- For any development standards, regulations and requirements not specifically shown on the SP plan and/or included as a condition of Commission or Council approval, the property shall be subject to the standards, regulations and requirements of the RM9 zoning district as of the date of the applicable request or application.
- ROW reservation intended to permit future extension of Seneca Drive.

Layout

SPECIFIC PLAN DEVELOPMENT SUMMARY

TOTAL SITE AREA:	2.04 ACRES
USE:	COTTAGES: SINGLE-FAMILY DETACHED RESIDENTIAL
PROPERTY ZONING:	SURROUNDING ZONING OL, CL, and R10
BULK STANDARDS:	
MINIMUM LOT SIZE:	NONE
NUMBER OF UNITS (DENSITY):	15 COTTAGES (7.4 DU/AC)
FAR:	0.40 MAXIMUM (0.31 PROPOSED)
ISR:	0.60 MAXIMUM (0.40 PROPOSED)
STREET SETBACKS:	16 FT. MINIMUM FROM LAKELAND 10 FT. MINIMUM FROM FUTURE SENECA DR. EXTENSION (IF CONSTRUCTED)
SIDE YARD SETBACK:	5 FT. MINIMUM FROM WESTERN BOUNDARY 10 FT. MINIMUM FROM EASTERN BOUNDARY
REAR YARD SETBACK:	10 FT. MINIMUM
MAXIMUM HEIGHT:	2 STORIES TO A MAXIMUM OF 30 FT. TO THE MEAN HEIGHT OF THE ROOF / UNITS FRONTING LAKELAND SHALL HAVE A HEIGHT APPEARANCE OF 1.5 STORIES
PERMITTED SETBACK ENCROACHMENTS:	ROOF OVERHANGS, STAIRS, COVERED STOOPS & PORCHES, CANOPIES, AND BAY WINDOWS - 5 FT.

PARKING AND ACCESS STANDARDS:	
RAMP LOCATION AND NUMBER:	3 DRIVEWAYS ON LAKELAND
DISTANCE TO NEAREST EXISTING RAMP FROM PROPERTY BOUNDARIES:	3.5 FT. FROM WESTERN PROPERTY BOUNDARY TO RESIDENTIAL DRIVEWAY 278.5 FT. FROM EASTERN PROPERTY BOUNDARY TO RESIDENTIAL DRIVEWAY
DISTANCE TO INTERSECTION FROM PROPERTY BOUNDARIES:	+/- 2,229 FT. WEST TO EMERY DRIVE +/- 461 FT. EAST TO DONELSON PIKE
REQUIRED PARKING BASED ON USES:	COTTAGES: 30 (2.0 SP/UNIT)
PROPOSED PARKING:	COTTAGES: 30 (2.0 SP/UNIT)

THIRD COAST DESIGN STUDIO
planning urban design architecture
1201 Villa Place Suite 104B
Nashville, Tennessee 37212
615.678.8640
This drawing shall not be reproduced, published, stored in an electronic retrieval system, or used in any way without the written permission of the Architect.
Copyright 2013 Third Coast Design Studio, LLC

410 DONELSON PIKE
Preliminary Specific Plan 2014SP-045-001
Being Parcel 74 on Tax Map 96-09
Nashville, Davidson County, Tennessee



DATE:	05.15.14	REVISIONS:	05.28.14
SET:	Preliminary SP	06.02.14	06.13.14